

Installation of Jupiter IDEAL EPS with Screed Replacement Tiles as sub floor. Covered with smoothing compound before linoleum application.



Laying the JUPITER pipe in the Jupiter IDEAL panels



Screed Replacement Tiles are glued together in brick bond format on the JUPIETR system foil.



Up to 400m² of Screed Replacement Tiles can be laid without the need for expansion gaps.



After 24 hours SRT's are set. filling compound such as Thomsit RS 88 is applied to ensure that any discrepancies do not show through the finished floor.



The linoleum is laid on the cured smoothing compound.

